

NOTICE INVITING QUOTATIONS


- A. Quotation for the Cost of Repair and Painting work of **School Boundary wall** for the area of **10720 Sq. feet.**
1. Sealed quotation for the above work whose detail is attached in page 2-3 is invited by the undersigned on behalf of the **SCS DAV Public School**, Haveli Kharagpur, Distt.- Munger up to 16.01.2026.
- B. Quotations should be sent in a sealed envelope marked as:

“ Quotation - Repair & Painting work of School Boundary wall ”

Quotation for providing for the cost of Repair & Painting work of Boundary wall of the School and not by name.

1. The quotations will be opened in the office of ARO, BR. DAV Public School, Begusarai on 17.01.2026 by the undersigned.
2. The quotations shall be submitted according to the terms and conditions specified in Paragraph 3 to 10. Unless specified otherwise in the quotations, it shall be construed that the terms and conditions stipulated hereunder have been agreed to.
3. The rates should be F.O.R. and should include all types taxes, rates or impositions which are liable., packing charges in respect of the supplies. The school/ institution shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation.
4. There should not be any overwriting or corrections in the quotation. If a figure is to be amended, it should be neatly scored out, the revised figure written above and the same attested with full signature and date. In the absence of such attestation the quotation is liable to be rejected.
5. The undersigned does not bind himself to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to all the articles mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
6. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation.
7. If the contractor fails to supply the articles within the time stipulated in the letter of Acceptance by the undersigned, the undersigned shall be at liberty to purchase the articles from the market or get the rest of contract completed by any other person or Firm.
8. Prior to acceptance of the quotation, the undersigned reserves the right to call for samples or demonstration and the contractor shall be liable to supply the samples or give the demonstration free of cost.
9. In the event of acceptance of the quotation and placing of the order for purchase, the articles ordered for would be subjected to an inspection by the undersigned or my representative and are liable to be rejected if the articles supplied are not according to approved samples or do not conform to the specification prescribed.
10. Quotations which do not comply with the above conditions are liable to be rejected.


Place: SCS DAV Public School, Haveli Kharagpur
Date: 05.01.2026


Dr. Subhash Chandra

Principal
SCS DAV Public School
Haveli Kharagpur
A# No. 330641

Sl.No.	S.O.R.	DESCRIPTION				
		1. COMPOUND WALL IN COLLAPSED PORTION				
		Compound wall length= 1305'-0"; Area of compound wall = 10720 Sft				
		Area of Compound wall painting = (70'+70')x18'+16'x(197'+53'+120'+58'+112'+336'+85'+204')=				
		21160SFT(1966.54 SM); 5'-6"x10"x10" Tana beams =30 No. ;10" dia Pile-30; Pile depth=12'-0"				
		Steel in pile- 10 mm dia -4 No.; Ring-6mm dia @ 6"c/c				
		SECTION-I (PILING/EARTH WORK/SAND FILLING)				
1	20.3A.1	Making 25cm (10") dia bore upto 4 mtr depth below ground with hand auger of approved quality in ordinary soil (Vide classification of soil item A) true to plumb and without eccentricity in any stage of operation and disposal of the excavated earth upto 50 mtr, lead in cluding all lifts all complete as per approved design and direction of E/I.	109.76	Rm		
		SECTION-II (P.C.C./R.C.C. WORK)				
2	5.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring , shuttering, finishing and reinforcement- All work up to plinth level				
	5.1.2	1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size)	5.52	Cum		
3	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centring, shuttering , finishing and reinforcement with 1:1.5:3 (1 cement :1.5 coarse sand: 3 graded stone aggregate 20mm nominal size).	3.22	Cum		
4	5.9	Centering and shuttering including strutting propping etc and removal of form for				
	5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	46.42	Sqm		
5	5.22	Reinforcement for R.C.C. work including straightening ,cutting ,bending,placing in position and binding all complete.				
	5.22.1B	Mild steel - 6mm dia.	248	Kg		
	5.22.7B	Thermo-Mechanically treated bars TMTC-500-	445	Kg		

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
		10mm dia.		
		SECTION-III (PLASTER WORK)		
6	13.11	12mm cement plaster of mix:		
	13.11.4	1:6 (1 cement; 6 coarse sand).	1029.70	Sqm
7	13.12.	15 mm cement plaster on rough side of single or half brick wall of mix.		
	13.12.4	1:6 (1 cement; 6 coarse sand).	983.27	Sqm
		SECTION-IV (FINISHING WORK)		
8	13.46A	Finishing walls with premium Acrylic Smooth exterior paint with silicone additives of required shade:		
	13.46A.1	New work(Two or more coat applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	2012.96	Sqm
		SECTION-V (DISMANTLING & DEMOLISHINGWORK)		
9	15.3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 meters lead:	0.32	Cum
10	15.56	Dismantling old plaster or skirting racking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	2012.96	Sqm


Headmaster
SCS DAV Public School
Haveli Kharagpur
Aff No.-330641